





**NOTES:**

1. DRIVEWAY TO BE PORTLAND CEMENT CONCRETE, MIN. 3000 P.S.I. @ 28 DAYS.
2. BASE TO BE A MINIMUM 4" OF CLEAN SAND OR SANDY LOAM, FULLY COMPACTED, FULL WIDTH.
3. CONCRETE TO BE BROOM FINISHED WITH EVEN, DUSTLESS SURFACE.

<b>PALM BEACH COUNTY DEPARTMENT OF ENGINEERING &amp; PUBLIC WORKS</b>				<b>RESIDENTIAL DRIVEWAY CURB &amp; GUTTER SECTION (CONCRETE)</b>		<b>DRAWING NO.</b>
DRAWN BY:	DATE:	REVISED BY:	DATE:	APPROVED:		EFFECTIVE:
<b>K.V.</b>	<b>05/23/90</b>					<b>300.IC</b>
REVISED BY:	DATE:			<b>COUNTY ENGINEER</b>		<b>08-01-90</b>